



Modular Carpet – Structures

SPECIFICATIONS

Product Line	Modular Carpet – Structures
Construction	Multilevel Scroll Loop
Backing System	PVC
Fiber System	100% Twisting Polypropylene
Pile Weight	17oz / 560g
Pile Height	0.2"-0.1"
Nominal Dimensions	20" wide x 20" long
Installation	Glue down
Recommended Adhesive	Taylor 2027
Indoor Air Quality	Green Label Plus
LEED Scorecard	EQ4.3

PACKAGING

Square Yards per Carton	6.171
Pieces per Carton	20
Weight per Carton	56 lbs

TESTING

Static Generation / AATCC 134	Passes
Radiant Flux / ASTM E648	Class II
Colorfastness to Light / AATCC 16	Passes
Smoke Density with Flaming / ASTM E662-97	Passes
Smoke Density / ASTM E662-97	Passes

WARRANTY

Manufacturer's Warranty	Lifetime
-------------------------	----------

Specifications are subject to nominal manufacturing variance. Material supply and/or manufacturing processes may necessitate changes without notice.